

In the matter of:	Johnson)	
)	
Serial No:)	Group Art Unit
)	Examiner:
Filed:	Herewith)	
)	
For:	An Electronic Device)	

PRELIMINARY AMENDMENT

Please preliminarily amend the above-referenced application as follows:

Please replace paragraph beginning at line 14 of page 1, with the following rewritten paragraph:

5

C:\WP51\AM2\915387PR AM2

Please replace paragraph beginning at line 8 of page 5, with the following rewritten paragraph:

Preferably, the recess is configured such that when the cover is mounted to the housing, a sound outlet is formed in the joint between the cover and the housing in the region of the recess. The aperture is most preferably a narrow slit and is largely obscured by the joint between the cover and the housing to prevent a user from being tempted to place this side of the telephone against the ear.

Please replace paragraph beginning at line 18 of page 7, with the following rewritten paragraph:

The inside face of the rear wall 12 is integrally formed with a seat to receive a transducer 16 having an upper surface 16a, illustrated in Figure 3. The transducer 16 is capable of relatively high acoustic volume and is used when the "hands free" mode is selected. The seat has an annular portion 17 against which the transducer 16 rests when placed on the housing 11 as shown in Figure 2. The annular portion 17 has an aperture 18 which acts as a duct for the transmission of sound generated by the transducer 16 through the rear wall 12 of the housing 11. The periphery of the annular portion 17 has an integrally formed upstanding wall 19 extending around its circumference having a top edge 20. The diameter of the annular portion 17 is slightly greater than the diameter of the transducer 16 which locates within the area enclosed by it on the annular portion 17.

Please replace paragraph beginning at line 17 at page 9, with the following rewritten paragraph:

Another embodiment will now be explained with reference to Figures 5, 6 and 7. It will be appreciated that this embodiment may or may not be combined with the first embodiment described with reference to Figures 2 to 4. However, it is envisaged that both embodiments will be used together.

In the Drawings:

Enclosed is a Submission of Proposed Drawing Amendment for Approval by Examiner (37 C.F.R. 1.123). The reason for this proposed drawing change is to have the identification of the arrows shown therein to be in conformance with the specification.

In the Claims:

11. (Amended) A device according to claim 10, wherein the spring comprises at least one region of the substantially planar annular ring which is deformed out of the plane of said ring, said region being deflected back toward the plane of said ring when in contact with the upper surface of a transducer and the retainer is rotated to attach it to the housing, the resilience of each of said at least one region biasing the transducer toward the housing.

24. (Amended) An electronic device comprising a housing, a cover, a transducer and a retainer for mounting the transducer on the housing, the retainer including a first

3 portion for co-operation with a second portion on the housing to attach the retainer to the
4 housing over the transducer;

5 wherein the housing has a recess formed therein, wherein the cover is mounted on the
6 housing over the recess, the cover and the housing together forming an acoustic duct in the
7 region of the recess.

1 25. (Amended) A mobile telephone comprising an electronic device having a
2 housing, a cover, a transducer and a retainer for mounting the transducer on the housing, the
3 retainer including a first portion for co-operation with a second portion on the housing to
4 attach the retainer to the housing over the transducer;

5 wherein the housing has a recess formed therein, wherein the cover is mounted on the
6 housing over the recess, the cover and the housing together forming an acoustic duct in the
7 region of the recess.

In the Abstract:

Please replace paragraphs beginning at lines 1 and 12 (combining both paragraphs) of page 15, with the following rewritten paragraph:

Abstract of the Disclosure

An electronic device including a housing, a transducer and a retainer for mounting the transducer on the housing (11) is disclosed. The device includes co-operating means (21,28) on the housing (11) and on the retainer (26) for attaching the retainer (26) to the housing (11) over the transducer (16). The retainer (26) is preferably attached to the housing (11) with a bayonet type fastener so that rotation of the retainer (26) against spring pressure positions lugs (28) on the retainer (26) in slots (22) on the housing (11). The present invention also discloses a housing (11) for a mobile telephone having a recess (39) therein and a cover (38) mounted on the housing (11) over the recess (39). The cover (38) and the housing (11) together form an acoustic duct in the region of the recess (39).

5

10
15
20
25
30
35
40
45
50
55
60
65
70
75
80
85
90
95
100
105
110
115
120
125
130
135
140
145
150
155
160
165
170
175
180
185
190
195
200
205
210
215
220
225
230
235
240
245
250
255
260
265
270
275
280
285
290
295
300
305
310
315
320
325
330
335
340
345
350
355
360
365
370
375
380
385
390
395
400
405
410
415
420
425
430
435
440
445
450
455
460
465
470
475
480
485
490
495
500
505
510
515
520
525
530
535
540
545
550
555
560
565
570
575
580
585
590
595
600
605
610
615
620
625
630
635
640
645
650
655
660
665
670
675
680
685
690
695
700
705
710
715
720
725
730
735
740
745
750
755
760
765
770
775
780
785
790
795
800
805
810
815
820
825
830
835
840
845
850
855
860
865
870
875
880
885
890
895
900
905
910
915
920
925
930
935
940
945
950
955
960
965
970
975
980
985
990
995
1000

20

Remarks


This amendment is filed for the purpose of placing the application into standard U.S. format and to eliminate any multiple dependent claims. Claims 11, 24 and 25 have been amended.

With respect to the drawings, the reason for this proposed drawing change is to have the identification of the arrows shown therein to be in conformance with the specification.

Attached hereto is a marked-up version of the changes made to the specification and claims by the current amendment. The attached page is captioned "Version with markings to show changes made."

Respectfully submitted,

Date: 6/28/2001


Alfred A. Fressola, Reg. No. 27,550
Ware, Fressola, Van Der Sluys
& Adolphson LLP
Bradford Green, Building Five
755 Main Street, PO Box 224
Monroe, CT 06468
(203) 261-1234

VERSION WITH MARKINGS TO SHOW CHANGES MADE

In the Specification:

Paragraph beginning at line 14 of page 1 has been amended as follows:

A transducer in a mobile telephone may be used to [fulfil] fulfill several functions in addition to the conversion of signals received by the telephone into speech so that the user can hear the person they are communicating with. For example, the transducer can also be used as a
5 buzzer to alert the owner to an incoming telephone call. This type of transducer is referred to as multi-functional.

Paragraph beginning at line 8 of page 5 has been amended as follows:

Preferably, the recess is configured such that when the cover is mounted to the housing, a
10 sound outlet is formed in the [join] joint between the cover and the housing in the region of the recess. The aperture is most preferably a narrow slit and is largely obscured by the [join] joint between the cover and the housing to prevent a user from being tempted to place this side of the telephone against the ear.

Paragraph beginning at line 18 of page 7 has been amended as follows:

The inside face of the rear wall 12 is integrally formed with a seat to receive a transducer 16
15 having an upper surface 16a, illustrated in Figure [2] 3. The transducer 16 is capable of relatively high acoustic volume and is used when the "hands free" mode is selected. The

seat has an annular portion 17 against which the transducer 16 rests when placed on the housing 11 as shown in Figure [3] 2. The annular portion 17 has an aperture 18 which acts as a duct for the transmission of sound generated by the transducer 16 through the rear wall 12 of the housing 11. The periphery of the annular portion 17 has an integrally formed upstanding wall 19 extending around its circumference having a top edge 20. The diameter of the annular portion 17 is slightly greater than the diameter of the transducer 16 which locates within the area enclosed by it on the annular portion 17.

Paragraph beginning at line 17 at page 9 has been amended as follows:

Another embodiment will now be explained with reference to Figures 5, 6 and 7. It will be appreciated that this embodiment [need] may or may not be combined with the first embodiment described with reference to Figures 2 to 4. However, it is envisaged that both embodiments will be used together.

In the Claims:

11. (Amended) A device according to claim 10, wherein the spring comprises at least one region of the substantially planar annular ring which is deformed out of the plane of said ring, said region being deflected back toward the plane of said ring when in contact with the upper surface of a transducer and the retainer is rotated to attach it to the housing, the resilience of [the or] each of said at least one region biasing the transducer toward the housing.

1 24. (Amended) An electronic device [according to claim 1] comprising a housing,
2 a cover, a transducer and a retainer for mounting the transducer on the housing, the retainer
3 including a first portion for co-operation with a second portion on the housing to attach the
4 retainer to the housing over the transducer; [and a housing according to claim 16]
5 wherein the housing has a recess formed therein, wherein the cover is mounted on the
6 housing over the recess, the cover and the housing together forming an acoustic duct in the
7 region of the recess.

1 25. (Amended) A mobile telephone comprising an electronic device [according to
2 claim 1] having a housing, a cover, a transducer and a retainer for mounting the transducer
3 on the housing, the retainer including a first portion for co-operation with a second portion
4 on the housing to attach the retainer to the housing over the transducer; [and a housing
5 according to claim 16]
6 wherein the housing has a recess formed therein, wherein the cover is mounted on the
7 housing over the recess, the cover and the housing together forming an acoustic duct in the
8 region of the recess.

In the Abstract:

Paragraph beginning at line 1 of page 15 has been amended as follows:

Abstract of the Disclosure

5 [An Electronic Device]

An electronic device including a housing, a transducer and a retainer for mounting the transducer on the housing (11) is disclosed. The device includes co-operating means (21,28) on the housing (11) and on the retainer (26) for attaching the retainer (26) to the housing (11) over the transducer (16). The retainer (26) is preferably attached to the housing (11) with a bayonet type fastener so that rotation of the retainer (26) against spring pressure positions lugs (28) on the retainer (26) in slots (22) on the housing (11).

[]

The present invention also discloses a housing (11) for a mobile telephone having a recess (39) therein and a cover (38) mounted on the housing (11) over the recess (39). The cover (38) and the housing (11) together form an acoustic duct in the region of the recess (39).

[Figure 3]

Practitioner's Docket No. 915.387

PATENT

IN THE UNITED STATES PATENT AND TRADEMARK OFFICE

In re application of: Keith JOHNSON
Application No.: 0 / Group No.:
Filed: Herewith Examiner:
For: An Electronic Device

Assistant Commissioner for Patents
Washington, D.C. 20231

**SUBMISSION OF PROPOSED DRAWING AMENDMENT
FOR APPROVAL BY EXAMINER (37 C.F.R. 1.123)**

Attached please find

(check applicable items)

- ☒ a sketch in permanent ink,
☐ a copy of the original drawing(s) with red ink markings,

showing the proposed changes to the drawing(s) in this application, for which the approval of the Examiner is requested.


SIGNATURE OF PRACTITIONER

Reg. No.: 27,550

Alfred A. Fressola
(type or print name of practitioner)

Tel. No.: (203) 261-1234

Ware, Fressola, Van Der Sluys & Adolphson LLP

Customer No.: 004955

P.O. Address
755 Main Street, Building Five
PO Box 224, Monroe, CT 06468

NOTE: 37 C.F.R. § 1.121(a)(3)(ii) indicates that "Where a change to the drawings is desired, a sketch in permanent ink showing proposed changes in red, to become part of the record, must be filed for approval by the examiner and should be in a separate paper."

NOTE: While drawings submitted under §§ 1.81, 1.83-1.85, 1.152, 1.165, 1.174, and 1.437 may not be filed by facsimile, proposed drawing corrections for approval may be submitted by facsimile transmission. Notice of Oct. 15, 1993, 58 Fed. Reg. 54,494-54,504, at 54,495.

CERTIFICATE OF MAILING/TRANSMISSION (37 C.F.R. 1.8(a))

I hereby certify that this correspondence is, on the date shown below, being:

MAILING

☒ deposited with the United States Postal Service with sufficient postage as first class mail, in an envelope addressed to the Assistant Commissioner for Patents, Washington, D.C. 20231.

FACSIMILE

☐ transmitted by facsimile to the Patent and Trademark Office.

Express Mail No. EL628641544US


Signature

Date: 6/28/01

Judith Schick
(type or print name of person certifying)

(Submission of Proposed Drawing Amendment for Approval by Examiner (37 C.F.R. 1.123) [9-16]—page 1 of 1)

FIG. 5

